Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 204	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 205	2	1	4.00		1.40	11.20	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-2	0.5	1.75		1.20	-2.10	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 206 A	2	1	12.10		3.50	84.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 206 B	2	1	8.30		3.50	58.10	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 207	2	1	3.90		3.50	27.30	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
				Total Executed Qty			**7639.50**			
				Schedule B Quantity			**5761.55**			
				Quantity Upto 125%			**7201.94**		**85.08**	**6,12,758.13**
				Quantity Above 125%			**437.56**		**85.08**	**37,228.50**
Item No. 63	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.and directions of the Engineer in charge.									
	RA Bill 03									
	Existing Degree College									
	Class Room 1	1	1	7.86		4.57	35.94	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	7.86		4.11	32.34	Sqm		
	Class Room 2	1	1	8.20		4.57	37.49	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
		2	1	7.05		4.34	61.24	Sqm		
		1	1	8.20		4.11	33.74	Sqm		
	Class Room 3	1	1	8.00		4.57	36.58	Sqm		
		2	1	7.05		4.34	61.24	Sqm		
		1	1	8.00		4.11	32.92	Sqm		
	Staff Room	1	1	3.90		4.57	17.83	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	3.90		4.11	16.05	Sqm		
	Class Room 4	1	1	8.20		4.57	37.49	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	8.20		4.11	33.74	Sqm		
	Class Room 5	1	1	8.02		4.57	36.67	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	8.02		4.11	33.00	Sqm		
	Class Room 6	1	1	8.20		4.57	37.49	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	8.20		4.11	33.74	Sqm		
	Class Room 7	1	1	9.00		4.57	41.15	Sqm		
		2	1	7.00		4.34	60.81	Sqm		
		1	1	9.00		4.11	37.03	Sqm		
		1	1	4.90		4.570	22.39	Sqm		
		2	1	0.60		4.340	5.21	Sqm		
	Deduction									
	Door (D)	-7	0.5	1.20		2.400	-10.08	Sqm		
	Door (D1)	-1	0.5	0.90		2.400	-1.08	Sqm		
	Window	-30	0.5	1.83		1.530	-42.00	Sqm		
				Total Executed Qty			**994.97**		98.17	97,677.98
				Schedule B Quantity			**1891.07**			
Item No. 64	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications page no117 item no 15.49.1 . KSRB 15-14.1 : Extra over Item 15-14.1 for applying oil bound washable distemper on ceiling and / or sloping roof as per specificationsand directions of the Engineer in charge.									
	RA BILL 3									
	Measurements taken on									
	Ceiling Painting									
	Proposed Building									
	Ground Floor									
	Corridor Walls at Entrance	1	1	6.90	1.50		10.35	Sqm		
	Additional Room Wall	1	1	3.50	3.10		10.85	Sqm		
				2.90	3.10		8.99	Sqm		
	Canteen	1	1	11.60	6.30		73.08	Sqm		
	Lobby Area	1	1	6.00	10.15		60.90	Sqm		
	Deduct Cutout Area	-1	1	9.20	0.6		-5.52	Sqm		
	Corridor infront of Staircase	1	1	12.10	3.60		43.56	Sqm		
	Store Room	1	1	5.00	3.00		15.00	Sqm		
	Corridor infront of Store	1	1	2.25	1.53		3.43	Sqm		
	Stair case Waist slab	2	1	3.75	1.50		11.25	Sqm		
	Landing	1	1	3.60	1.50		5.40	Sqm		
	First Floor									
	Class Room 1	1	1	8.75	6.3		55.13	Sqm		
	Class Room 2	1	1	8.75	6.3		55.13	Sqm		
	Class Room 3	1	1	8.75	6.3		55.13	Sqm		
	Class Room 4	1	1	8.75	6.3		55.13	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Corridor	1	1	12.90	3.6		46.44	Sqm		
	Deduct Cutout Area	-1	1	9.20	0.6		-5.52	Sqm		
	Stair case Waist slab	2	1	3.75	1.50		11.25	Sqm		
	Landing	1	1	3.60	1.50		5.40	Sqm		
	Second Floor									
	Class Room 1	1	1	8.75	6.3		55.13	Sqm		
	Class Room 2	1	1	8.75	6.3		55.13	Sqm		
	Class Room 3	1	1	8.75	6.3		55.13	Sqm		
	Class Room 4	1	1	8.75	6.3		55.13	Sqm		
	Corridor	1	1	12.90	3.6		46.44	Sqm		
	Deduct Cutout Area	-1	1	9.20	0.6		-5.52	Sqm		
	Stair case Waist slab	2	1	3.75	1.50		11.25	Sqm		
	Landing	1	1	3.60	1.50		5.40	Sqm		
	Third Floor									
	Class Room 1	1	1	8.75	6.3		55.13	Sqm		
	Class Room 2	1	1	8.75	6.3		55.13	Sqm		
	Class Room 3	1	1	8.75	6.3		55.13	Sqm		
	Class Room 4	1	1	8.75	6.3		55.13	Sqm		
	Corridor	1	1	12.90	3.6		46.44	Sqm		
	Deduct Cutout Area	-1	1	9.20	0.6		-5.52	Sqm		
	Terrace Floor									
	Head Room	1	1	3.60	5.15		18.54	Sqm		
	Existing Building-I									
	Ceiling Painting									
	Ground Floor									
	Library	2	1	16.40	6.70		219.76	Sqm		
		2	1	8.00	6.70		107.20	Sqm		
	Principal Room	2	1	5.10	6.70		68.34	Sqm		
	Room No 11	2	1	8.00	6.70		107.20	Sqm		
	Room No 10	2	1	8.15	6.70		109.21	Sqm		
	Room No 9	2	1	8.00	6.70		107.20	Sqm		
	Staircase Waist slab	2	1	3.75	1.50					
	Corridor	2	1	67.00	1.85		247.90	Sqm		
	First Floor									
	Room No 117	2	1	8.00	6.70		107.20	Sqm		
	Room No 116	2	1	8.10	6.70		108.54	Sqm		
	Room No 115	2	1	8.00	6.70		107.20	Sqm		
	Room No 114	2	1	8.10	6.70		108.54	Sqm		
	Room No 113	2	1	3.80	6.70		50.92	Sqm		
	Room No 112	2	1	8.10	6.70		108.54	Sqm		
	Room No 111	2	1	8.10	6.70		108.54	Sqm		
	Room No 110	2	1	8.10	6.70		108.54	Sqm		
	Corridor	2	1	62.00	1.85		229.40	Sqm		
	Second Floor									
	Room No 201	2	1	9.00	6.70		120.60	Sqm		
	Room No 202	2	1	8.10	6.70		108.54	Sqm		
	Room No 203	2	1	8.00	6.70		107.20	Sqm		
	Room No 204 / 212	2	1	8.00	6.70		107.20	Sqm		
	Room No 205 / 211	2	1	3.85	6.70		51.59	Sqm		
	Room No 210	2	1	8.00	6.70		107.20	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Room No 209	2	1	8.00	6.70		107.20	Sqm		
	Room No 208	2	1	8.00	6.70		107.20	Sqm		
	Corridor	2	1	65.80	6.70		881.72	Sqm		
	Existing Building-II									
	Ceiling Painting									
	Ground Floor									
	Room No 001	1	1	7.00	6.7		46.90	Sqm		
	Room No 002	1	1	7.00	6.7		46.90	Sqm		
	Room No 003	1	1	7.00	6.7		46.90	Sqm		
	Room No 004	1	1	8.00	6.7		53.60	Sqm		
	Room No 005	1	1	7.00	6.7		46.90	Sqm		
	Room No 006	1	1	12.10	6.7		81.07	Sqm		
	Room No 007	1	1	8.00	6.7		53.60	Sqm		
	Room No 008	1	1	7.00	6.7		46.90	Sqm		
	Staircase Waist slab	2	1	3.75	1.5		11.25	Sqm		
	Landing	1	1	3.00	1.5		4.50	Sqm		
	First Floor									
	Room No 101	1	1	8.00	6.7		53.60	Sqm		
	Room No 102	1	1	7.00	6.7		46.90	Sqm		
	Room No 103	1	1	8.00	6.7		53.60	Sqm		
	Room No 104	1	1	7.00	6.7		46.90	Sqm		
	Room No 105	1	1	8.00	6.7		53.60	Sqm		
	Room No 106	1	1	3.65	6.7		24.46	Sqm		
	Room No 107	1	1	8.00	6.7		53.60	Sqm		
	Room No 108	1	1	8.00	6.7		53.60	Sqm		
	Room No 109	1	1	8.00	6.7		53.60	Sqm		
	Staircase Waist slab	2	1	3.75	1.5		11.25	Sqm		
	Landing	1	1	3.00	1.5		4.50	Sqm		
	Second Floor									
	Room No 201	1	1	8.00	6.7		53.60	Sqm		
	Room No 202	1	1	8.00	6.7		53.60	Sqm		
	Room No 203	1	1	8.00	6.7		53.60	Sqm		
	Room No 204	1	1	8.00	6.7		53.60	Sqm		
	Room No 205	1	1	4.00	6.7		26.80	Sqm		
	Room No 206 A	1	1	12.10	6.7		81.07	Sqm		
	Room No 206 B	1	1	8.30	6.7		55.61	Sqm		
	Room No 207	1	1	3.90	6.7		26.13	Sqm		
	Staircase Waist slab	2	1	3.75	1.5		11.25	Sqm		
	Landing	1	1	3.00	1.5		4.50	Sqm		
	Wall Painting									
	Proposed Building									
	Ground Floor									
	Corridor Walls at Entrance	2	1	6.90		1.40	19.32	Sqm		
	Lobby at Ground Floor									
	Additional Room Wall	1	1	3.30		1.40	4.62	Sqm		
	Left side Wall at Lobby	1	1	10.15		1.40	14.21	Sqm		
	Rear Wall	1	1	5.85		1.40	8.19	Sqm		
	Gents Toilet Wall at Lobby	1	1	6.65		1.40	9.31	Sqm		
	Gents Toilet Wall at Staircase	1	1	4.65		1.40	6.51	Sqm		
	Infront of Store room	1	1	1.53		1.40	2.14	Sqm		
		1	1	2.25		1.40	3.15	Sqm		
		1	1	1.16		1.40	1.62	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Staircase Area, For Canteen	1	1	12.10		1.40	16.94	Sqm		
	Store Room Inside	1	2	5.00		1.40	14.00	Sqm		
		1	2	3.00		1.40	8.40	Sqm		
	Canteen Inside	1	2	11.60		1.40	32.48	Sqm		
		1	2	6.30		1.40	17.64	Sqm		
	Additional Room Inside	1	1	3.50		1.40	4.90	Sqm		
		1	1	3.10		1.40	4.34	Sqm		
		1	2	2.90		2.00	11.60	Sqm		
		1	2	3.10		2.00	12.40	Sqm		
	Gents Toilet									
	W/C inside	5	4	1.20		1.40	33.60	Sqm		
	Corridor wall infront of W/C	1	1	5.20		1.40	7.28	Sqm		
	W/C Side wall	1	1	1.30		1.40	1.82	Sqm		
	Partition Wall infront of W/C	1	2	4.10		1.40	11.48	Sqm		
	Urinals Wall	1	1	6.30		1.40	8.82	Sqm		
	Wall @ Wash Basin	1	1	4.20		1.40	5.88	Sqm		
	Entrance wall	1	1	1.40		1.40	1.96	Sqm		
	Ladies Toilet									
	W/C inside	8	4	1.20		1.40	53.76	Sqm		
	Corridor infront of W/C's	2	1	5.00		1.40	14.00	Sqm		
	Wash Basin Wall	1	1	4.00		1.40	5.60	Sqm		
	Entrance wall	1	1	1.20		1.40	1.68	Sqm		
	Stair case									
	Side Wall @ Base Landing	1	1	1.50		1.70	2.55	Sqm		
	Side Wall @ Steps	2	1	3.85		1.95	15.02	Sqm		
	Side Wall @ Landing	2	1	1.50		2.00	6.00	Sqm		
		1	1	3.60		2.00	7.20	Sqm		
	First Floor									
	Class Room 1	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 2	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 3	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 4	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	D	-4	0.5	1.50		1.20	-3.60	Sqm		
	W1	-18	0.5	1.83		1.53	-25.20	Sqm		
	W2	-2	0.5	1.50		1.53	-2.30	Sqm		
	Corridor									
	Classroom Wall Both side	2	1	12.90		2.00	51.60	Sqm		
	At Window Side	1	1	3.40		2.00	6.80	Sqm		
	W1	-2	0.5	1.83		1.53	-2.80	Sqm		
	D	-4	0.5	1.50		2.00	-6.00	Sqm		
	Stair case									
	Side Wall @ Steps	2	1	3.85		2.00	15.40	Sqm		
	Side Wall @ Landing	2	1	1.50		2.05	6.15	Sqm		
		1	1	3.60		2.05	7.38	Sqm		
	Second Floor									
	Class Room 1	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 2	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 3	2	1	8.75		2.60	45.50	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 4	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	D	-4	0.5	1.50		1.20	-3.60	Sqm		
	W1	-18	0.5	1.83		1.53	-25.20	Sqm		
	W2	-2	0.5	1.50		1.53	-2.30	Sqm		
	Corridor									
	Classroom Wall Both side	2	1	12.90		2.00	51.60	Sqm		
	At Window Side	1	1	3.40		2.00	6.80	Sqm		
	W1	-2	0.5	1.83		1.53	-2.80	Sqm		
	D	-4	0.5	1.50		2.00	-6.00	Sqm		
	Stair case									
	Side Wall @ Steps	2	1	3.85		2.00	15.40	Sqm		
	Side Wall @ Landing	2	1	1.50		2.05	6.15	Sqm		
		1	1	3.60		2.05	7.38	Sqm		
	Third Floor									
	Class Room 1	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 2	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 3	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	Class Room 4	2	1	8.75		2.60	45.50	Sqm		
		2	1	6.30		2.60	32.76	Sqm		
	D	-4	0.5	1.50		1.20	-3.60	Sqm		
	W1	-18	0.5	1.83		1.53	-25.20	Sqm		
	W2	-2	0.5	1.50		1.53	-2.30	Sqm		
	Corridor									
	Classroom Wall Both side	2	1	12.90		2.00	51.60	Sqm		
	At Window Side	1	1	3.40		2.00	6.80	Sqm		
	W1	-2	0.5	1.83		1.53	-2.80	Sqm		
	D	-4	0.5	1.50		2.00	-6.00	Sqm		
	Stair case									
	Side Wall @ Steps	2	1	3.85		2.00	15.40	Sqm		
	Side Wall @ Landing	2	1	1.50		2.05	6.15	Sqm		
		1	1	3.60		2.05	7.38	Sqm		
	Terrace Floor									
	Head Room									
	Along Grid 3	1	1	3.60		3.18	11.43	Sqm		
	Along Grid 4	1	1	3.60		3.18	11.43	Sqm		
	Along Grid B	1	1	5.15		3.18	16.35	Sqm		
	Along Grid C	1	1	5.15		3.18	16.35	Sqm		
	Deduction Door (D1)	-1	1	1.20		2.10	-1.26	Sqm		
	Existing College Building-I									
	Ground Floor									
	Wall Painting									
	Library	2	1	16.40		3.50	114.80	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
		2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduct Opening	1	2	2.50		3.00	15.00	Sqm		
	Add jambs	1	1	11.00		0.23	2.53	Sqm		
	Door D	-3	0.5	1.50		2.50	-5.63	Sqm		
	Windows W	-15	0.5	1.75		1.50	-19.69	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Principal Room	2	1	5.10		3.50	35.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Door D	-1	0.5	1.50		2.10	-1.58	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
		-2	0.5	0.60		1.50	-0.90	Sqm		
	Room No 11	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 10	2	1	8.15		3.50	57.05	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 9	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	NSS Block (Right side of									
	Staircase Side Walls	1	2	7.20		3.50	50.40	Sqm		
	Window side wall	1	1	3.00		3.50	10.50	Sqm		
	W	-1	0.5	1.85		1.50	-1.39	Sqm		
	Waist slab bottom	1	1	7.20	3.00		21.60	Sqm		
	First Floor									
	Room No 117	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-6	0.5	1.75		1.50	-7.88	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 116	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 115	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 114	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 113	2	1	3.80		1.40	10.64	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-1	0.5	0.75		1.20	-0.45	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 112	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 111	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 110	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	NSS Block (Right side of									
	Staircase Side Walls	1	2	7.20		3.50	50.40	Sqm		
	Window side wall	1	1	3.00		3.50	10.50	Sqm		
	W	-1	0.5	1.85		1.50	-1.39	Sqm		
	Waist slab bottom	1	1	7.20	3.00		21.60	Sqm		
	Second Floor									
	Room No 201	2	1	9.00		3.50	63.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-6	0.5	1.75		1.50	-7.88	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 202	2	1	8.10		3.50	56.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 203	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 204 / 212	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 205 / 211	2	1	3.85		1.40	10.78	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-1	0.5	0.75		1.20	-0.45	Sqm		
	Ventelator V	-2	0.5	0.60		1.00	-0.60	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 210	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 209	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 208	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	NSS Block (Right side of									
	Staircase Side Walls	1	2	7.20		3.50	50.40	Sqm		
	Window side wall	1	1	3.00		3.50	10.50	Sqm		
	W	-1	0.5	1.85		1.50	-1.39	Sqm		
	Waist slab bottom	1	1	7.20	3.00		21.60	Sqm		
	Existing College Building-II									
	Ground Floor									
	Wall Painting									
	Room No 001	2	1	7.00		3.50	49.00	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 002	2	1	7.00		3.50	49.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 003	2	1	7.00		3.50	49.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 004	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 005	2	1	7.00		1.40	19.60	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-4	0.5	1.75		1.20	-4.20	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 006	2	1	12.10		3.50	84.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-6	0.5	1.75		1.50	-7.88	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 007	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 008	2	1	7.00		3.50	49.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	First Floor									

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Wall Painting									
	Room No 101	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 102	2	1	7.00		3.50	49.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 103	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 104	2	1	7.00		3.50	49.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 105	2	1	8.00		1.40	22.40	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-4	0.5	1.75		1.20	-4.20	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 106	2	1	3.65		3.50	25.55	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 107	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 108	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Room No 109	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Second Floor									
	Wall Painting									
	Room No 201	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 202	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 203	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 204	2	1	8.00		3.50	56.00	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 205	2	1	4.00		1.40	11.20	Sqm		
		2	1	6.70		1.40	18.76	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W1	-2	0.5	1.75		1.20	-2.10	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 206 A	2	1	12.10		3.50	84.70	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 206 B	2	1	8.30		3.50	58.10	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Windows W	-4	0.5	1.75		1.50	-5.25	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Room No 207	2	1	3.90		3.50	27.30	Sqm		
		2	1	6.70		3.50	46.90	Sqm		
	Deduction									
	Door D	-1	0.5	1.50		2.50	-1.88	Sqm		
	Windows W	-2	0.5	1.75		1.50	-2.63	Sqm		
	Chock Board	-1	1	2.40		1.20	-2.88	Sqm		
	Existing College Building-									
	Ground Floor									
	Wall Painting	1	2	8.20		3.50	57.40	Sqm		
		1	1	3.00		3.50	10.50	Sqm		
	Paassage	1	1	1.40		3.50	4.90	Sqm		
		1	1	1.20		3.50	4.20	Sqm		
	Waist slab Bottom	1	1	8.20		3.00	24.60	Sqm		
	Deduction									
	window	-1	1	1.80		1.50	-2.70	Sqm		
	First Floor									
	Wall Painting	1	2	8.20		3.50	57.40	Sqm		
		1	1	3.00		3.50	10.50	Sqm		
	Paassage	1	1	1.40		3.50	4.90	Sqm		
		1	1	1.20		3.50	4.20	Sqm		
	Waist slab Bottom	1	1	8.20		3.00	24.60	Sqm		
	window	-1	1	1.80		1.50	-2.70	Sqm		
	Second Floor									
	Wall Painting	1	2	8.20		3.50	57.40	Sqm		
		1	1	3.00		3.50	10.50	Sqm		
	Paassage	1	1	1.40		3.50	4.90	Sqm		
		1	1	1.20		3.50	4.20	Sqm		
	Waist slab Bottom	1	1	8.20		3.00	24.60	Sqm		
	window	-1	1	1.80		1.50	-2.70	Sqm		
				Total Executed Qty			**12192.73**			
				Schedule B Quantity			**1374.92**			
				Quantity Upto 125%			**1718.65**		**128.71**	**2,21,215.00**
				Quantity Above 125%			**10474.08**		**128.71**	**13,48,165.02**
Item No. 65	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specifications and directions of the Engineer in charge.									
	RA Bill 03									
	External Wall Painting									
	Ground Floor									
	Along Grid A & D	2	1	18		3.65	131.40	Sqm		
	Along Grid 1 & 4	2	1	17		3.65	124.10	Sqm		
	Deduction									
	Along Grid A									
	Opening	-1	1	5.7		3.05	-17.39	Sqm		
	Add Jambs	1	1	11.8		0.20	2.36	Sqm		
	Window (W1)	-12	0.5	1.83		1.53	-16.80	Sqm		
	Door (D)	-1	1	2.2		2.10	-4.62	Sqm		
	Add Jambs	1	1	6.5		0.20	1.30	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Door (D2)	-1	0.5	0.75		2.10	-0.79	Sqm		
	Ventilator (V)	-6	0.5	0.75		0.60	-1.35	Sqm		
	Existing College Building-I									
	External Paint									
	Front side	1	1	70.72		3.65	258.13	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.50		1.53	-5.36	Sqm		
	Add jambs	1	2	5.03	0.115		1.16	Sqm		
	W2	-1	1	3.38		1.53	-5.17	Sqm		
	Add jambs	1	2	4.91	0.115		1.13	Sqm		
	W3	-1	1	3.50		1.53	-5.36	Sqm		
	Add jambs	1	2	5.03	0.115		1.16	Sqm		
	D1	-1	1	3.89		2.50	-9.73	Sqm		
	Add jambs	1	2	6.39	0.115		1.47	Sqm		
	W4	-1	1	3.47		1.53	-5.31	Sqm		
	Add jambs	1	2	5.00	0.115		1.15	Sqm		
	W5	-1	1	3.39		1.53	-5.19	Sqm		
	Add jambs	1	2	4.92	0.115		1.13	Sqm		
	W6	-1	1	3.52		1.53	-5.39	Sqm		
	Add jambs	1	2	5.05	0.115		1.16	Sqm		
	W7	-1	1	3.48		1.53	-5.32	Sqm		
	Add jambs	1	2	5.01	0.115		1.15	Sqm		
	D2	-1	1	3.15		2.50	-7.88	Sqm		
	Add jambs	1	2	5.65	0.115		1.30	Sqm		
	W8	-1	1	2.83		1.53	-4.33	Sqm		
	Add jambs	1	2	4.36	0.115		1.00	Sqm		
	W9	-1	1	1.07		1.53	-1.64	Sqm		
	Add jambs	1	2	2.60	0.115		0.60	Sqm		
	W10	-1	1	2.39		1.53	-3.66	Sqm		
	Add jambs	1	2	3.92	0.115		0.90	Sqm		
	W11	-1	1	3.38		1.53	-5.17	Sqm		
	Add jambs	1	2	4.91	0.115		1.13	Sqm		
	W12	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	D3	-1	1	3.85		2.50	-9.63	Sqm		
	Add jambs	1	2	6.35	0.115		1.46	Sqm		
	W13	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W13	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.88	0.115		1.12	Sqm		
	Existing College Building-II									
	External Paint									
	Front side	1	1	66.26		3.65	241.85	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W2	-1	1	3.15		1.53	-4.82	Sqm		
	Add jambs	1	2	4.68	0.115		1.08	Sqm		
	W3	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W4	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	W5	-1	1	3.13		1.53	-4.79	Sqm		
	Add jambs	1	2	3.40	0.115		0.78	Sqm		
	W6	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W7	-1	1	3.03		2.40	-7.27	Sqm		
	Add jambs	1	2	5.43	0.115		1.25	Sqm		
	W8	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W9	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W10	-1	1	3.37		1.53	-5.16	Sqm		
	Add jambs	1	2	4.90	0.115		1.13	Sqm		
	W11	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W12	-1	1	3.80		1.53	-5.81	Sqm		
	Add jambs	1	2	5.33	0.115		1.23	Sqm		
	W13	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W14	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W15	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W16	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W16	-1	1	1.10		1.45	-1.60	Sqm		
	Add jambs	1	2	2.55	0.115		0.59	Sqm		
				Total Executed Qty			**575.30**		**370.87**	**2,13,361.55**
				Schedule B Quantity			**614.58**			
Item No. 66	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specificationsand directions of the Engineer in charge.(First Floor)									
	RA Bill 03									
	External Wall Painting									
	First Floor									
	Along Grid A & D	2	1	18		3.65	131.40	Sqm		
	Along Grid 1 & 4	2	1	17		3.65	124.10	Sqm		
	Deduction									
	Window (W1)	-18	0.5	1.83		1.53	-25.20	Sqm		
	Window (W2)	-2	0.5	1.2		1.50	-1.80	Sqm		
	Existing College Building-I									
	External Paint									
	Front side	1	1	82.96		3.65	302.80	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.35		1.53	-5.13	Sqm		
	Add jambs	1	2	4.88	0.115		1.12	Sqm		
	W2	-1	1	3.46		1.53	-5.29	Sqm		
	Add jambs	1	2	4.99	0.115		1.15	Sqm		
	W3	-1	1	3.45		1.53	-5.28	Sqm		
	Add jambs	1	2	4.98	0.115		1.15	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	W4	-1	1	3.45		1.53	-5.28	Sqm		
	Add jambs	1	2	4.98	0.115		1.15	Sqm		
	W5	-1	1	3.35		1.53	-5.13	Sqm		
	Add jambs	1	2	4.88	0.115		1.12	Sqm		
	W6	-1	1	3.47		1.53	-5.31	Sqm		
	Add jambs	1	2	5.00	0.115		1.15	Sqm		
	W7	-1	1	3.47		1.53	-5.31	Sqm		
	Add jambs	1	2	5.00	0.115		1.15	Sqm		
	W8	-1	1	2.74		1.53	-4.19	Sqm		
	Add jambs	1	2	4.27	0.115		0.98	Sqm		
	W9	-1	1	2.77		1.53	-4.24	Sqm		
	Add jambs	1	2	4.30	0.115		0.99	Sqm		
	W10	-1	1	1.07		1.53	-1.64	Sqm		
	Add jambs	1	2	2.60	0.115		0.60	Sqm		
	W11	-1	1	3.38		1.53	-5.17	Sqm		
	Add jambs	1	2	4.91	0.115		1.13	Sqm		
	W12	-1	1	3.42		1.53	-5.23	Sqm		
	Add jambs	1	2	4.95	0.115		1.14	Sqm		
	W13	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W14	-1	1	3.36		1.53	-5.14	Sqm		
	Add jambs	1	2	4.89	0.115		1.12	Sqm		
	W15	-1	1	3.32		1.53	-5.08	Sqm		
	Add jambs	1	2	4.85	0.115		1.12	Sqm		
	W16	-1	1	3.37		1.53	-5.16	Sqm		
	Add jambs	1	2	4.90	0.115		1.13	Sqm		
	Existing College Building-II									
	External Paint									
	Front side	1	1	66.26		3.65	241.85	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W2	-1	1	3.15		1.53	-4.82	Sqm		
	Add jambs	1	2	4.68	0.115		1.08	Sqm		
	W3	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W4	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W5	-1	1	3.13		1.53	-4.79	Sqm		
	Add jambs	1	2	3.40	0.115		0.78	Sqm		
	W6	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W7	-1	1	3.03		1.53	-4.64	Sqm		
	Add jambs	1	2	4.56	0.115		1.05	Sqm		
	W8	-1	1	3.30		1.53	-5.05	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W9	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W10	-1	1	3.37		1.53	-5.16	Sqm		
	Add jambs	1	2	4.90	0.115		1.13	Sqm		
	W11	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W12	-1	1	3.80		1.53	-5.81	Sqm		
	Add jambs	1	2	5.33	0.115		1.23	Sqm		
	W13	-1	1	3.40		2.50	-8.50	Sqm		
	Add jambs	1	2	5.90	0.115		1.36	Sqm		
	W14	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W15	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W16	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W17	-1	1	1.10		1.45	-1.60	Sqm		
	Add jambs	1	2	2.55	0.115		0.59	Sqm		
				Total Executed Qty			**644.31**		**379.60**	**2,44,578.48**
				Schedule B Quantity			**487.35**			
Item No. 67	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specifications and directions of the Engineer in charge.(Second Floor)									
	Measurements taken on									
	External Wall Painting									
	Second Floor									
	Along Grid A & D	2	1	18		3.65	131.40	Sqm		
	Along Grid 1 & 4	2	1	17		3.65	124.10	Sqm		
	Deduction									
	Window (W1)	-18	0.5	1.83		1.53	-25.20	Sqm		
	Window (W2)	-2	0.5	1.2		1.50	-1.80	Sqm		
	Existing College Building-I									
	External Paint									
	Front side	1	1	82.96		3.65	302.80	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.48		1.53	-5.32	Sqm		
	Add jambs	1	2	5.01	0.115		1.15	Sqm		
	W2	-1	1	3.34		1.53	-5.11	Sqm		
	Add jambs	1	2	4.87	0.115		1.12	Sqm		
	W3	-1	1	3.45		1.53	-5.28	Sqm		
	Add jambs	1	2	4.98	0.115		1.15	Sqm		
	W4	-1	1	3.45		1.53	-5.28	Sqm		
	Add jambs	1	2	4.98	0.115		1.15	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	W5	-1	1	3.45		1.53	-5.28	Sqm		
	Add jambs	1	2	4.98	0.115		1.15	Sqm		
	W6	-1	1	3.35		1.53	-5.13	Sqm		
	Add jambs	1	2	4.88	0.115		1.12	Sqm		
	W7	-1	1	3.46		1.53	-5.29	Sqm		
	Add jambs	1	2	4.99	0.115		1.15	Sqm		
	W8	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W9	-1	1	3.16		1.53	-4.83	Sqm		
	Add jambs	1	2	4.69	0.115		1.08	Sqm		
	W10	-1	1	1.75		1.53	-2.68	Sqm		
	Add jambs	1	2	3.28	0.115		0.75	Sqm		
	W11	-1	1	0.86		1.53	-1.32	Sqm		
	Add jambs	1	2	2.39	0.115		0.55	Sqm		
	W12	-1	1	3.36		1.37	-4.60	Sqm		
	Add jambs	1	2	4.73	0.115		1.09	Sqm		
	W13	-1	1	3.43		1.37	-4.70	Sqm		
	Add jambs	1	2	4.80	0.115		1.10	Sqm		
	W14	-1	1	3.38		1.37	-4.63	Sqm		
	Add jambs	1	2	4.75	0.115		1.09	Sqm		
	W15	-1	1	3.40		1.37	-4.66	Sqm		
	Add jambs	1	2	4.77	0.115		1.10	Sqm		
	W16	-1	1	3.37		1.37	-4.62	Sqm		
	Add jambs	1	2	4.74	0.115		1.09	Sqm		
	W17	-1	1	3.38		1.37	-4.63	Sqm		
	Add jambs	1	2	4.75	0.115		1.09	Sqm		
	Existing College Building-II									
	External Paint									
	Front side	1	1	66.26		3.65	241.85	Sqm		
	Deductions									
	Openings (Window & Door									
	W1	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W2	-1	1	3.15		1.53	-4.82	Sqm		
	Add jambs	1	2	4.68	0.115		1.08	Sqm		
	W3	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W4	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W5	-1	1	3.13		1.53	-4.79	Sqm		
	Add jambs	1	2	3.40	0.115		0.78	Sqm		
	W6	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W7	-1	1	3.03		1.53	-4.64	Sqm		
	Add jambs	1	2	4.56	0.115		1.05	Sqm		
	W8	-1	1	3.30		1.53	-5.05	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W9	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W10	-1	1	3.37		1.53	-5.16	Sqm		
	Add jambs	1	2	4.90	0.115		1.13	Sqm		
	W11	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W12	-1	1	3.80		1.53	-5.81	Sqm		
	Add jambs	1	2	5.33	0.115		1.23	Sqm		
	W13	-1	1	3.40		2.50	-8.50	Sqm		
	Add jambs	1	2	5.90	0.115		1.36	Sqm		
	W14	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W15	-1	1	3.30		1.53	-5.05	Sqm		
	Add jambs	1	2	4.83	0.115		1.11	Sqm		
	W16	-1	1	3.40		1.53	-5.20	Sqm		
	Add jambs	1	2	4.93	0.115		1.13	Sqm		
	W17	-1	1	1.10		1.45	-1.60	Sqm		
	Add jambs	1	2	2.55	0.115		0.59	Sqm		
				Total Executed Qty			**644.26**			
				Schedule B Quantity			**489.03**			
				Quantity Upto 125%			**611.29**		388.32	2,37,378.10
				Quantity Above 125%			**32.97**		388.32	12,803.57
Item No. 68	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specificationsand directions of the Engineer in charge.(Third Floor)									
	RA Bill 02									
	External Wall Painting									
	Existing Degree College									
	Along Long walls - Front side	1	1	63.05		3.265	205.85	Sqm		
	Rear Wall	1	1	63.05		4.573	288.34	Sqm		
	Along Short Walls	1	2	9.05		4.343	78.62	Sqm		
	Corridor parapet wall	1	1	3		0.85	2.55	Sqm		
	Window (W1)	-30	0.5	1.8		1.5	-40.50	Sqm		
	Measurements taken on									
	External Wall Painting									
	Third Floor									
	Along Grid A & D	2	1	18		3.65	131.40	Sqm		
	Along Grid 1 & 4	2	1	17		3.65	124.10	Sqm		
	Deduction									
	Window (W1)	-18	0.5	1.83		1.53	-25.20	Sqm		
	Window (W2)	-2	0.5	1.2		1.50	-1.80	Sqm		
	Existing College Building-I									
	External Paint									
	Front side Parapet Wall	1	1	67.46		0.90	60.71	Sqm		
	Front side Parapet Wall of	1	2	15.50		0.90	27.90	Sqm		
	Existing College Building-II									
	External Paint									
	Front side Parapet Wall	1	1	66.26		1.10	72.89	Sqm		

Scanned by TapScanner

Item No	Description of Item	No	No	Length (M)	Breadth (M)	Depth (M)	Quantity	Unit	Rate	Amount
					Total Executed Qty		**924.85**		**397.05**	**3,67,213.00**
					Schedule B Quantity		**1147.66**			
Item No. 69	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specificationsand directions of the Engineer in charge.(Head room)									
	RA Bill 03									
	External Wall Painting									
	Terrace Floor									
	Head Room									
	Along Grid 3	1	1	4.2		3.35	14.07	Sqm		
	Along Grid 4	1	1	4.2		3.35	14.07	Sqm		
	Along Grid B	1	1	5.45		3.35	18.26	Sqm		
	Column Sides	2	1	0.15		3.35	1.01	Sqm		
	Along Grid C	1	1	5.45		3.35	18.26	Sqm		
	Column Sides	2	1	0.15		3.35	1.01	Sqm		
	Parapet Wall									
	Along Grid A & D	2	2	18		1.12	80.64	Sqm		
	Along Grid 1	1	2	17		1.12	38.08	Sqm		
	Along Grid 4	1	2	12.8		1.12	28.67	Sqm		
	Head Room Parapet	2	2	6.15		0.60	14.76	Sqm		
		2	2	4.05		0.60	9.72	Sqm		
	Cut out Parapet wall									
	Long wall	1	2	9.2		0.90	16.56	Sqm		
		1	2	9.2		0.85	15.64	Sqm		
	Short wall - Outside	2	2	0.8		0.88	2.80	Sqm		
	inside	2	2	0.6		0.88	2.10	Sqm		
	Top portion	1	1	19.6		0.10	1.96	Sqm		
	Deduction									
	Along Grid A									
	Door (D1)	-1	1	1.2		2.10	-2.52	Sqm		
					Total Executed Qty		**275.08**		**405.78**	**1,11,620.08**
					Schedule B Quantity		**271.90**			
Item No. 70	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,complete as per									
	RA Bill 03									
	Staircase									
	Ground to First Floor									
	Staircase									
	Risers	22	1	1.50		0.15	4.95	Sqm		
	Treads	22	1	1.50	0.30		9.90	Sqm		
	Landing	1	1	3.60	1.50		5.40	Sqm		
					Total Executed Qty		**20.25**		**4,860.60**	**98,427.25**
					Schedule B Quantity		**50.23**			
Item No. 71	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,complete as per									
	RA Bill 03									
	Stair case									
	First to Second Floor									
	Staircase									

Scanned by TapScanner